## Horizon Structural Systems Inc.

3950 Hwy 46 West #200, New Braunfels, TX 78132

830-629-8000

https://horizonstructural.com

info@horizonstructural.com

# HORIZON STRUCTURAL SYSTEMS, INC.

#### DUE TO THE PROCESS OF CONTINUOUS IMPROVEMENT, THE PRODUCTS AND PROCEDURES IN THIS MANUAL ARE SUBJECT TO CHANGE <u>WITHOUT</u> NOTICE

MANUAL REVISION INFORMATION			
ΑCTIVITY	ADDENDUM RELEASE #	PAGES REVISED	RELEASE DATE
Revised	#1	All	08/31/2018

NOTES

# TABLE OF CONTENTS

1.0	General	
1.1	Purpose of this manual	
1.2	Buyer's responsibility	
1.3	MBMA	4
1.4	Disclaimer	4
1.5	Receiving and shipping	
1.6	Handling and Storage	5
1.7	Insurance	5
1.8	Power supply	5
1.9	Electrical service and cords	5
1.10	Electrical safety and cord clearance	5
1.11	Roof performance	5
2.0	Importance of Seaming/Hand Crimping	6
2.1	When to hand crimp	6
2.2	When to seam	6
2.3	Specialized seaming tools	6
2.4	Crimping/Seaming Requirements	7
3.0	Glossary of Terms	8
4.0	Finished Seam Types	9
4.1	General	9
4.2	Horizon RollLok Seam	
4.3	Horizon TripleLok Seam	9
4.4	Horizon QuadLok Seam	9
4.5	Seam type details	10
5.0	Seaming Kit	11
5.1	Specialized seaming tools	11
5.2	Seaming tool source	11
5.3	Seaming kit	11
6.0	Assembly	13
6.1	Side lap fit-up	
6.2	Clip alignment	13
6.3	Seam damage	
7.0	Horizon RollLok/TripleLok Crimper Tools (Buyout items)	
7.1	Stand-up Roll Lock/TripleLok hand crimper	
7.2	Small Roll Lock/TripleLok hand crimper	
8.0	Manual Crimping Tool Operation for Schulte RollLok/TripleLok (Small Crimper)	15
8.1	Small hand crimping tool nomenclature	15
8.2	Assemble the crimping tool	15
8.3	Tool orientation to seam	
8.4	Forming the seam	15
8.5	Tool position on the roof panel	16
8.6	Checking the finished seam	16
9.0	Manual Crimping Tool Operation for Horizon RollLok/TripleLok (Stand-up Crimper)	17

9.1	Stand-up hand crimping tool nomenclature	. 17
9.2	Assemble the stand-up crimping tool	. 17
9.3	Tool orientation to the seam	. 17
9.4	Forming the seam	. 17
10.0	Horizon RollLok Seaming Details	. 18
10.1	Manual seaming	. 18
10.2	Finished seam detail	. 18
11.0	Before Operating the Motorized Seaming Machine	. 19
11.1	Seaming machine nomenclature	. 19
11.2	Single direction TripleLok seamer	19
11.3	Flip Flop Seamer (Bi-Directional)	20
11.4	Cleaning the seams	. 20
11.5	Starting seams	
11.6	Single direction QuadLok seamer	. 21
12.0	Motorized Seaming Machine (TripleLok)	22
12.1	Manual crimping/seaming	
12.2	Machine orientation to the seam (single directional seamer)	
12.3	Machine position on the roof panel	
12.4	Machine orientation to the seam (bi-directional seamer)	
12.5	Rotating the bi-directional seamer	
12.6	Machine position on the roof panel	
12.7	Running the machine	
12.8	Unlocking the machine	
12.9	Stopping the machine	
	Checking the finished seam	
13.0	QuadLok Crimper Tools (Buyout Items)	
14.0	Manual Crimping Tool Operation for QuadLok (Small Crimper)	
14.1	Tool orientation to seam	
15.0	Manual Crimping Tool Operation for Horizon QuadLok (Stand-up Crimper)	
15.1	Stand-up hand crimping tool nomenclature	
15.2	Assemble the stand-up crimping tool	
15.3	Tool orientation to the seam	
	Forming the seam	
16.0	QuadLok Seaming Details (Single Pass Operation)	
16.1	Locking seamer on panel	
16.2	Motor seaming	
17.0	QuadLok Seaming Details (Double Pass Operation)	
17.1	Prior seaming	
17.2	Locking seamer on panel	
17.3	Motor seaming	
17.4	Finished seam detail	
18.0	Motorized Seaming Machine Maintenance	. 32
18.1	General	
18.2	Seaming rolls	
18.3	Cooling vents	
19.0	Seamer Troubleshooting Guide	. 33

## 1.0 General

#### 1.1 Purpose of this manual

This installation manual is provided to Horizon Builders and their erectors as the recommended procedure for the correct seaming of the Horizon Structural Systems (HSS) Panel Craft Roof System.

This manual is intended to be used in conjunction with the Panel Craft Installation Manual and the project's erection drawings to help plan and organize the installation of the HSS Panel Craft Roof System. The erection drawings govern specific seam requirements. In the case of conflict between this installation manual and the erection drawings, the erection drawings will take precedence.

#### 1.2 Buyer's Responsibility

The buyer must take responsibility for selecting a competent erector, insist that the work be performed by qualified and experienced standing seam metal roof installers, and insist that the erector take time to study and understand this manual, then assure that the erector correctly follows the manual's instructions.

Horizon does not guarantee and is not liable for the quality of the erection. HSS is not responsible for building defects that may be attributed to improper erection or negligence of other parties.

Clarification concerning the HSS Panel Craft roof installation should be directed to the Horizon Structural Systems Customer Service Department. The following is a list of addresses and phone numbers for the customer service representative at each division:

#### Horizon Structural Systems Inc.

3950 Hwy 46 West #200, New Braunfels, TX 78132

830-629-8000

https://horizonstructural.com

info@horizonstructural.com

#### 1.3 MBMA

This building is designed, manufactured and delivered in accordance with the 2006 M.B.M.A. (Metal Building Manufacturer's Association) metal Structural Systems manual. Consult the information in the "Common Industry Practices" section for more information.

#### 1.4 Disclaimer

# THE PRODUCTS AND PROCEDURES IN THIS MANUAL ARE SUBJECT TO CHANGE <u>WITHOUT</u> NOTICE.

#### 1.5 Receiving and Shipping

Upon receipt of the seaming kit, and before the signing of the shipping receipt, check and verify that the seaming kit is received in good condition, without damage or loss of contents. See section 5.0 for a list of kit contents.

If there is damage or loss of contents, immediately file the claim with the shipper and notify the seamer supplier or HSS for replacement instructions.

Upon completion of seaming the roof, promptly return the seaming kit to the seamer supplier in accordance with the instructions on the return shipping documents. The return shipping documents are included in the seaming kit.

1.6 Handling and Storage	1.9 Electrical Service and Cords
Provide safe and secure handling of the seaming tools when in	The electrical service and cords to the seaming machine <b>MUST</b>
use.	be of sufficient capacity to provide the full 20-amps @ 120-
	volts <u>AT THE SEAMING MACHINE.</u> If other tools or equipment
The meterized economics mechine unishe CC neurode, and econ	
The motorized seaming machine weighs 65-pounds, and can	are being used on the same service, the service and cord
cause severe injury and damage if it falls.	capacity <b>MUST</b> be increased accordingly.
The machine is too heavy to safely carry up a ladder. Always	IMPORTANT NOTE: Low voltage due to insufficient service
hoist the machine onto the roof with proper lifting equipment	capacity, insufficient cord size or excessive cord length will
and securely tied to the machine's front lifting handle.	cause overheating and burnout of the seaming machine's motor.
When starting and stopping the seaming machine at the edges	
of the roof, the operator must be securely positioned so they	Cord Requirements for proper voltage chart
can safely lift the machine on and off of the panel seam.	
<b>Caution:</b> When running the machine in the downslope	Distance (Ft.) 0-50 50-100 100-200 200-300 wire
direction, the machine will have greater downhill inertia and	Gauge(AWG) 12 10 8 6
coasting distance.	
When not locked to the panel seam, the motorized seaming	1.10 Electrical Safety and Cord Clearance
machine can freely roll on its wheels. Always secure the	Check that the power cords are fitted with the correct plug for
	safe and secure connection to the seaming machine. Check
machine to prevent it from rolling or sliding off of the roof.	that the power cords are properly grounded and that the
	service has a ground fault circuit breaker.
When the seaming tools are not in use, they must be stored in	service has a ground fault circuit breaker.
the seaming kit chest and in a safe and dry area. The seaming	Check that the cleatrical and is of sufficient length to sut and
tools MUST be cleaned and dried before storing.	Check that the electrical cord is of sufficient length to extend
	the full length of the area to be seamed, without stress on the
1.7 Insurance	cord or its connections. Check that the path for the cord is
The HSS seaming tools are custom built specialized	clear and that the cord is clear of snagging on panel edges or
equipment and are costly to replace. Provide adequate	entanglement onto the seaming machine rolls.
insurance coverage on the seaming tools while they are in	
your possession.	1.11 Roof Performance
	The roof panels <b>MUST</b> be correctly installed, hand crimped, and
1.8 Power Supply	seamed before the roof system can provide its designed wind
The seaming machine motor requires a minimum electrical	load and weather resistance capability. This means that an un-
power supply of:	seamed roof is subject to wind load failure. The erector shall
20 amps @ 120 volt @ 60 hz. AC.	be responsible to ensure that the proper seaming method is
	followed (Either Horizon RollLok, TripleLok, or QuadLok).
	······

2.0 Importance of Seaming/Hand Crimping	2.3 Specialized Seaming Tools
<b>2.1 When to Hand Crimp</b> As work progresses, the erector <u>is required</u> to hand crimp the panels at the low eave, each panel clip, each end lap and high eave/ridge end of the panels. Utilize the proper hand crimper to accomplish this RollLok profile.	On roofs requiring the TripleLok or QuadLok seams, it may not always be practical or feasible to motor seam the roof panels until after the roof installation is completed. Motor seamed roof panels are difficult to reposition or replace. Motorized seaming machines may not always be available during the entire roof installation period.
Hand crimping the entire roof into a finished RollLok seam, will suffice in <i>temporarily securing the roof panel until the proper finished seam can be completed</i> . Also, hand crimping at the required locations is required <b>PRIOR</b> to motor seaming of the seaf seamed.	In such cases, it may be desirable to temporarily RollLok (hand crimp) the roof panels with the manual seaming tool. Then later complete the seaming with the motorized seaming machine.
<ul> <li>roof panel.</li> <li>2.2 When to Seam</li> <li>Whenever possible, the installed roof panels should be seamed at the completion of each day's work. If high winds or rain/snow conditions are imminent, the installed roof panels must be seamed before such conditions occur.</li> </ul>	IMPORTANT: It shall be the erector's responsibility to apply the RollLok seaming method in such a way as to ensure that the panels have been adequately secured until the motor seaming can occur.
Refer to the project erection drawing <b>ROOF SHEETING PLAN(S)</b> and/or <b>DETAIL PAGE(S)</b> to determine what seaming option is required. The detail on the next page is a copy of the detail that will appear on the erection drawings. <b>NOTE:</b> This detail conveys the <u>MINIMUM</u> seaming requirements based on the design of the project. Additional seaming may be necessary as specified by the builder. ALSO NOTE: Multiple seaming types may be required on a project. Review the roof sheeting plan(s) and detail(s) carefully. Multiple seam types means that you could have two different seamers each producing a different seam profile. See page 11 defining seam types.	

Panel Craft CRIMPING/SEAMING REQUIREMENTS

## THE DESIGN OF THIS STRUCTURE REQUIRES THAT THE FOLLOWING SEAMING METHOD BE UTILIZED:

- 1. 🗌 Roll Lock Seam
- 2. TripleLok Seam
- 3. 🔲 QuadLok Seam

NOTE 1: Additional seaming may be necessary as specified by the builder.

<u>NOTE 2</u>: Multiple seaming types may be required. Review the roof seaming plan(s) carefully for seaming requirements.

<u>NOTE 3</u>: NOT all roof systems require mechanical seaming. The buyer, owner, or architect may elect to specify a mechanically seamed panel. Often, factory mutual ratings also require a QuadLok mechanical seamer.

#### SEE THE Panel Craft SEAMING MANUAL FOR IMPORTANT ERECTOR INFORMATION ABOUT QUADLOK SEAMER REQUIREMENTS.

#### When to crimp/seam

As work progresses, it shall be the erector's responsibility to apply the RollLok hand crimping method in as required to ensure that the panels have been adequately secured until mechanical seaming can occur.

Whenever possible, the installed roof panels should be mechanically seamed as work progresses OR at the completion of each day's work. If high winds or rain/snow conditions are imminent, the installed roof panels must be seamed before such conditions occur.

Refer to the project erection drawing roof seaming plan and/or detail pages to determine what option is required. The above detail conveys the MINIMUM seaming requirements based upon the design of the project. Additional seaming may be required on a project. Review the roof seaming plan(s) and details.

#### 3.0 Glossary of Terms:

Below is a list of terms and nomenclature used within this manual to describe hand crimping and seaming operations.

Panel Seam – Male and female panel corrugation properly hooked together over a clip within a roof system.

**Finished Panel Seam** – A seam that has been completely or partly hand crimped OR motorized seamed into a RollLok, TripleLok or QuadLok profile seam.

**RollLok Seam** – A finished seam that has had a series of *single* hand crimps at the low eave, each clip, end lap and high eave/ridge of each panel with a RollLok/TripleLok hand crimper.

Manual Seaming – The crimping of a panel by use of a hand crimper.

Temporary Crimping – A finished RollLok seam.

Motor/Mechanical Seaming – Seaming the panel by use of an electric panel seamer.

**TripleLok Seam** – A finished seam that has been hand crimped *continuously* with a TripleLok hand crimper OR motorized seamed with a TripleLok seamer.

**QuadLok Seam** – A finished seam that has been hand crimped *continuously* with a QuadLok hand crimper OR motorized seamed with a QuadLok seamer.

**Single Pass QuadLok Seamer Operation** – A single seamer that is setup to form a Roll Lock seam into a QuadLok seam in one pass. (One direction ONLY)

"The Answer" – The seamer suppliers name for a single pass QuadLok seamer.

**Double Pass QuadLok Seamer Operation** – Two separate seamers are required. One is set-up for the TripleLok seam and the second seamer is set-up for the QuadLok seam. (One direction only on the second seamer)

Primary Seamer – This is the first seamer in a double pass seaming operation and is set-up to produce a TripleLok seam.

**Secondary Seamer** – This is the second seamer in a double pass seaming operation and is set-up to produce a QuadLok seam.


Single Directional Seamer – A seamer that completes a finished seam in a single direction.

Flip-flop Seamer (Bi-Directional) - A seamer that has two sets of tooling that runs two directions.

This seamer can be set-up to have TripleLok tooling on **both** sides of the machine, allowing it to TripleLok a seam in one direction, then being flipped over and placed on the next seam over to run back the other direction, producing another TripleLok seam.

This seamer can be set-up to have one side of the tooling set-up for TripleLok and the other side of the tooling set-up for QuadLok. This type of seamer will run one direction producing a TripleLok seam. Then it can be flipped over and placed back on the *same* TripleLok seam and ran back on the seam to the beginning thus producing a QuadLok 360 seam.

4.0 Finished Seam Types	4.4 QuadLok Seam
	Single pass QuadLok seamer operation
4.1 General	This is a single seamer that is set-up to form a RollLok seam
The HSS Panel Craft roof system has three seam type options.	into a QuadLok seam in one pass.
The project design and performance requirements govern	
which finished seam type is required.	Double pass QuadLok seamer operation
which misned searn type is required.	This will require the use of two seamers. The primary seaming
Different finished seam types may be required on specific areas	tool will form the TripleLok seam and then the secondary
	seaming tool will form the QuadLok.
of the roof. In all cases, refer to the erection drawings to	
determine the required seam type and locations.	This seaming method requires that the roof panels be
4.2 Dellick Geom	previously seamed to the TripleLok seam profile. Then over-
4.2 RollLok Seam	seaming the full length of the roof panels with the motorized
The RollLok seam requires the roof panels be crimped with the	seaming machine.
manual seaming tools at the panel clips, low eave, high side of	
the roof panels, and at the end laps. This is <u>required</u> to be	To start the QuadLok seamer, the previously TripleLok panel
completed as the roof is being installed or by the end of each	seam will need to be manually crimped with the QuadLok hand
work day.	crimper. (Just to start the seamer) See pages 27-30 for
	instructions.
The single hand crimp forms the seam into a TripleLok profile.	
	NOTE:
The motorized seaming machine <b>MUST</b> have these locations	A QuadLok seam can be <i>achieved</i> by <b>continually</b> hand crimping
hand crimped <u>before</u> it is placed into operation.	the TripleLok seam with the QuadLok hand crimper.
	the impletok seam with the Quadtok hand chinper.
4.3 TripleLok Seam	SEE THE FOLLOWING PAGE FOR DETAILS OF ALL THREE SEAM
The TripleLok seam requires crimping the roof panels with the	TYPES.
manual seaming tool at the panel clips, low eave, high side of	
the roof panels, and at the end laps. Then seaming the full	
length of the roof panels with the motorized seaming machine.	
NOTE:	
A TripleLok seam can be <i>achieved</i> by <b>continually</b> hand crimping	
the roof panel lap with the correct hand crimper.	



## 5.0 Seaming Kit

#### 5.1 Specialized Seaming Tools

The seaming of the HSS Panel Craft roof panels requires special seaming tools that are available only from HSS.

#### CAUTION:

THE USE OF ANY OTHER SEAMING EQUIPMENT WILL RESULT IN FAULTY AND/OR DAMAGED SEAMS AND SHALL INVALIDATE THE ROOF SYSTEM'S MATERIAL AND WEATHER TIGHTNESS WARRANTIES.

#### 5.2 Seaming Tool Source

The seaming tools are provided by HSS in accordance with the terms and conditions of the HSS contract documents. Contact the HSS Customer Services Department to arrange the scheduling, delivery and return of the seaming tools.







Small TripleLok Hand Crimper (Included in the Seamer Kit)



Small QuadLok Hand Crimper (Included in the Seamer Kit)

#### 5.3 Seaming Kit

The seaming equipment will normally be provided as a seaming kit. The seaming kit will include the following:

- Seaming kit chest (contains and protects the seaming tools during shipment and storage).
- Manual crimping tool(s)
- Motorized seaming machine (provided only for HSS seaming applications).
- Seaming instructions manual
- Return shipping documents
- Small tool kit which includes; miscellaneous wrenches, replacement fiber backer rollers and cam rollers.



Single Directional Motorized Seaming Machine (Produces a TripleLok Seam)


#### Seaming Kit Continued



Bi-directional Motorized Seaming Machine Produces a TripleLok Seam (TripleLok Tooling on BOTH sides)



Single Directional Motorized Seaming Machine Produces a QuadLok Seam (For a Two Pass Operation)



## 7.0 RollLok/TripleLok Crimper Tools (Buyout Items)

#### 7.1 Stand-up RollLok/TripleLok Hand Crimper

Per the order documents, your job may have one or more of these crimpers.



Stand-up RollLok/TripleLok Hand Crimper

#### 7.2 Small RollLok/TripleLok Hand Crimper


Per the order documents, your job may have one or more of these crimpers. This crimper is useful for one person erecting the low eave, end laps, high eave ends of the panels and during roof curb installations.






Small RollLok/TripleLok Hand Crimper


8.0 MANUAL CRIMPING TOOL OPERATION FOR THE	8.3 Tool Orientation to Seam
ROLLLOK/TRIPLELOK SMALL CRIMPER	Orient the tool to fit correctly onto the roof panel seam as
	shown in Step 1 below. The stationary handle <b>MUST</b> be in the
8.1 Small Hand Crimping Tool Nomenclature	horizontal position and the operating handle <b>MUST</b> be rotated
The detail below identifies the operational parts of the small hand crimping tool.	up to the open position.
	8.4 Forming the Seam
This hand crimper manually forms a finished TripleLok seam if used continuously.	When the tool is correctly positioned on the panel, push the stationary blade solidly against the top of the seam.
<b>8.2</b> Assemble the Crimping Tool When received, the crimping tool may be disassembled. Assemble the handle to the tool body with the provided bolts.	While holding the stationary handle in the horizontal position, rotate the operating handle down to the horizontal position as shown in Step 2. This will form the seam into a <i>single</i> TripleLok crimp.
Operating Handle	-Assembly Bolts




<ul> <li>8.5 Tool Position on the Roof Panel</li> <li>When hand crimping at the low eave, ridge end, end lap and</li> <li>ALL roof clip locations, the crimping MUST be done in two steps.</li> <li>Step 1: Position the crimping tool as shown below in the various areas of the roof. Rotate the moveable handle down to form a single TripleLok crimp. Release the handle.</li> </ul>	<ul> <li>Step 2: Re-position the crimping tool as shown below and repeat Step 1.</li> <li>8.6 Checking the Finished Seam Rotate the operating handle to the open position, remove the tool and check that the seam is correctly formed, as shown below.</li> </ul>
------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------



9.0 MANUAL CRIMPING TOOL OPERTION FOR THE	9.4 Forming the Seam
ROLLLOK/TRIPLELOK STAND-UP CRIMPER	The tool is correctly positioned on the panel seam when the
	operating handle is UP and the stationary shoe is pushed firmly
9.1 Stand-up Hand Crimping Tool Nomenclature	DOWN against the top of the seam.
The detail below identifies the operational parts of the stand-	
up hand crimping tool.	While holding the stationary handle vertical, rotate the
	operating handle DOWN to the position as shown in Step 2.
9.2 Assemble the Stand-up Crimping Tool	This will form the seam into a <i>single</i> TripleLok shaped crimp.
When received, the crimping tool may be partially	
disassembled. Assemble the handle to the push rod with the	NOTE:
provided lock pins.	This hand crimper manually forms a finished RollLok seam and
	if used continuously, will form a finished TripleLok seam.
9.3 Tool Orientation to the Seam	
Orient the tool to fit correctly onto the roof panel seam as	CAUTION:
shown in Step 1 below. The stationary handle <b>MUST</b> be in the	The crimper or seam could be damaged if the stationary shoe
vertical position and the operating handle <b>MUST</b> be rotated to	is NOT COMPLETELY down on the seam.
the open position.	





#### 11.0 BEFORE OPERATING THE MOTORIZED SEAMING MACHINE

## 11.1 Seaming Machine Nomenclature

The following pages identify the operational parts of different motorized seaming machines. Familiarize yourself with the supplied seamer prior to operation. Seaming tools may have slight variations from the tools shown in this manual.




**11.2** Single Direction TripleLok Seamer With a single directional TripleLok seamer, it should be clearly labeled "PRIMARY" on the tool with arrows indicating the direction of travel. (see below)





11.3 Flip Flop Seamer (Bi-Directional)	11.4 Cleaning the Seams
This seamer machine has two sets of forming rollers on one	The roof panel seams MUST be thoroughly cleaned of abrasive
machine. This tool can be started at the peak or the eave.	dirt or dust that can cause scuffing or scratching of the seam
Arrows indicate the direction of travel. Once the seamer	surface. The roof panel seams MUST be cleaned of grease and
machine has finished TripleLoking a seam, un-lock the machine	ALL other contaminants that can cause the seaming machine
from the seam, then pull up on the release trigger pin located	slippage and marking of the seam surface.
under the handle. Rotate the machine until the machine	suppuge and marking of the seam surface.
trigger pin locks into position once the machine has been	11.5 Starting Seams
	0
rotated. Next, lock the seamer on the next seam adjacent to	For the TripleLok seaming, the seaming machine MUST start on
the one that was just seamed.	a finished RollLok seam that has already been crimped with the
MAKE SURE THAT THE SEAMER ARROW POINTS IN THE	manual crimping tool. Depending on which direction the
DIRECTION OF THE PANEL THAT IS TO BE SEAMED. Double	seaming machine will run, form the starting seam at the eave
check that the rollers are properly placed on the panel seam as	or ridge end of the panels with the manual seaming tool as
shown in Sections 12.4-12.6. Seam the panel and then repeat	described previously in Sections 7.0-9.0.
the prior steps on the next seam.	
	NOTE:
	IF excessive picking of the paint or Galvalume coating is
	occurring, then discontinue seaming and consult with your
	HSS customer service representative or your seamer supplier
	representative. Failure to contact either representative may
	void your roof warranty.



#### 11.6 Single Direction QuadLok Seamer

Used in the double pass QuadLok operation.

The QuadLok seam requires one three station OR one four station single direction motorized seaming tool. These tools will be clearly labeled **"Primary"** and **"Secondary"** with arrows indicating the direction of travel.

The Primary seaming tool MUST be run on ALL panels BEFORE the Secondary seaming tool is operated.



## **Secondary Seamer**

## **Single Directional Motorized Seaming Machine**

## Produces a QuadLok Seam


12.0 MOTORIZED SEAMING MACHINE (TRIPLELOK)	12.3 Machine Position on the Roof Panel
	NOTE:
12.1 Manual Crimping/Seaming	Prior to running the seamer, make sure a safety cable is
The TripleLok seam requires prior hand crimping of the roof	attached to the seamer.
panel with the manual seaming tool at ALL panel clips, low	
eave, high side of the roof panels, and at the end laps. Then	With the locking handles down in the open position, set the
seaming the full length of the roof panels with the motorized	seaming machine onto the starting end of the roof panel's
seaming machine.	seam, over the manually seamed portion of the seam.
12.2 Machine Orientation to the Seam (Single Directional	Roll the seaming machine forward to align the front seaming
Seamer)	rolls over the unseamed portion of the seam, as shown in the
On roofs sheeted from left to right, the seaming machine will	details below.
run from the eave to the ridge.	
On roofs sheeted from right to left, the seaming machine will	
run from the ridge to the eave.	



Seamer Locked on the Manually Crimped VR16 II panel

> Seamer Direction

Note the Orientation of the Seamer



Unlocked Handles Down Locked Front Two Handles Up

Seamer Locked on the Adjacent Seam

12.4 Machine Orientation to the Seam (Bi-Directional Seamer)

With this example below, the Flip-Flop seamer produces a TripleLok seam in **both** directions. When using the Bi-Directional seamer, it doesn't matter which direction that the roof was sheeted. The seamer will run from eave to ridge OR ridge to eave.



Step #1

With the locking handle held up in the open position, set the seaming machine onto the starting end of the roof panel's seam, over the manually crimped portion of the seam. Shown is the TS-324 Panel for example only


Basically, you run the seamer up one seam, release the trigger pin next to the handle, rotate the machine, then place it on the adjacent un-seamed seam and run the seamer back.

The Seaming Direction is Indicated by Arrows on the Motor.



Step #2

Lock the seamer onto the panel by pushing the handle outward.



#### **12.5** Rotating the Bi-Directional Seamer



Step #5

Next, un-lock the seamer from the panel seam. Pull up on the trigger pin next to the handle.

Step #6

Rotate the seamer 180°, allowing the trigger pin to latch.



Step #7

The seamer fully rotated.

## **12.6** Machine Positioning on the Roof Panel



Step #8

Place rotated seamer on the adjacent seam. Lock onto manually crimped area of the panel. Shown is the TS-324 Panel for example only



#### Step #9

Seamer ran back to starting point on the adjacent seam. Repeat steps 1-9 along the panel run

<ul> <li>12.7 Running the Seaming Machine Check that the machine's path is clear of power cords, tools, debris, etc.</li> <li>Start the machine by turning on the machine's toggle switch. When running the seamer, the operator should look ahead of the seamer for any damaged seams or un-engaged panels. If the operator sees damaged and/or un-engaged panels, then the operator should stop the machine and fix the problem area <i>BEFORE</i> continuing. FAILURE to repair such areas and then running the seamer over them could cause the seam to become un-repairable.</li> <li>Watch the machine and the finished seam carefully for any indication of the machine malfunctioning or faulty seaming.</li> <li>CAUTION: <ul> <li>Check that ALL seams have been properly hand crimped PRIOR to motor seaming.</li> <li>STOP the machine immediately, and investigate any indications of machine malfunction or faulty seaming.</li> <li>It is recommended NOT to run the seamer over panel end laps. The end laps should be hand crimped for proper finished seam.</li> <li>Do not run the machine into previously installed outside closures, roof curbs or other obstructions.</li> <li>Do not run the machine over damaged seams or un- hooked panels.</li> <li>Do not walk or stand on the panel NEXT to the machine while it is running.</li> <li>The seaming machine MUST ALWAYS be in the vertical position while seaming. Do Not allow the machine to tilt sideways when locking the machine onto the seam or while the machine is running. On roofs with tall clips, walking or standing on the panel next to the machine can deflect the panel and cause the machine to tilt.</li> </ul> </li> </ul>	<ul> <li>12.8 Unlocking the Machine After the machine is turned off and has fully stopped, release the locking handle to the open position. With the locking handle released, the machine can be lifted from the seam. If the machine must be stopped and removed before completing the seam, use a felt marker to mark the position of the machine's font wheel on the panel. The machine can later be repositioned on the mark to complete the seaming. 12.9 Stopping the Machine Stop the machine by turning off the machine's toggle switch. ALWAYS allow sufficient space for the machine to coast after turning it off. 12.10 Checking the Finished Seam At the completion of each seam, check the full length of the seam for any false seaming or distortions. Refer to Sections 10.2, 12.3, &amp; 17.4 for details of correctly formed finished seams. NOTE: Seaming options vary from project to project. Refer to the project erection drawings for specific seaming requirements for your project. Finished TripleLok Seam Aright TripleLok Seam</li></ul>

## 13.0 QUADLOK CRIMPER TOOLS (BUYOUT ITEMS)



Small QuadLok Hand Crimper


Stand-up QuadLok Hand Crimper




Open Crimping Jaw of the QuadLok Crimper

14.0 MANUAL CRIMPING TOOL OPERATION FOR THE QUADLOK (SMALL CRIMPER)	Next, apply outward and downward pressure to the handles to start folding down the top rib. Continue the outward and downward pressure until the panel rib is flat.
<ul> <li>14.1 Tool Orientation to Seam</li> <li>Next is the process of manually crimping the panel rib into a 360° seam profile. Before you attempt the QuadLok hand crimper: check and see if you have a good tight TripleLok seam. If not, then go over the area with a TripleLok hand crimper and re-crimp. It is important to manually crimp a single QuadLok crimp PRIOR to locking on and running the QuadLok seamer.</li> <li>Start by placing the open 360° crimper on top of the previously TripleLoked panel rib and between a roof clip. Make sure that the flat side of the crimper is on the panel rib shoulder and the crimper hook is under the female lip. Note the angle of the crimper.</li> </ul>	NOTE: DO NOT use this crimper to temporarily hand crimp any part of the panel seam.

## Small QuadLok Hand Crimper




15.0 MANUAL CRIMPING TOOL OPERATION FOR THE	15.4 Forming the Seam		
QUADLOK ( STAND-UP CRIMPER)	The tool is correctly positioned on the panel seam, when the operating handle is UP and the stationary shoe is DOWN		
15.1 Stand-up Hand Crimping Tool Nomenclature	against the top of the seam.		
The detail below identifies the operational parts of the stand-			
up crimping tool.	While holding the stationary handle vertical, rotate the		
	operating handle down to the position as shown in Step 2. This		
15.2 Assemble the Stand-up Crimping Tool	will form the seam into a single QuadLok shaped crimp profile.		
When received, the crimping tool may be partially			
disassembled. Assemble the handle to the push rod with the	NOTE:		
provided lock pins.	This hand crimper is meant to be used continuously and by doing so, will form a finished QuadLok seam. This crimper is for		
15.3 Tool Orientation to the Seam	hand crimping small edges, corner zones, and for locating the		
Orient the tool to fit correctly onto the roof panel seam as	QuadLok seamer onto the seam.		
shown in Step 1 below. The stationary handle MUST be in the			
vertical position and the operating handle MUST be rotated up	CAUTION:		
to the open position.	The crimper or seam could be damaged, if the stationary shoe		
	is NOT COMPLETELY down on the seam.		




16.0 QUADLOK SEAMING DETAILS (SINGLE PASS	Finish by locking down handles 2 & 3. Make sure that the		
OPERTION)	number one station has engaged the panel (as shown below).		
16.1 Locking Seamer on Panel	16.2 Motor Seaming		
Prior to running a single directional QuadLok seamer, you	Once the seamer is properly locked on the pre-crimped seam,		
MUST hand crimp or electrically seam the entire roof into a	switch the machine on and seam the full length of each roof		
finished RollLok/TripleLok seam profile. To start the QuadLok	panel.		
seamer, you need to hand crimp a small area with a QuadLok			
hand crimper (as shown below). After the QuadLok hand	The seamer will run from eave to ridge OR ridge to eave,		
crimping has been completed, place the QuadLok seamer on	depending on the way the roof panels were installed.		
the panel rib, aligning the number four station roller over the			
previously QuadLok hand crimped area. (NOTE: Make sure	NOTE:		
the arrow on the seamer is pointing in the direction you are	It is recommended <b>NOT</b> to run the seamer over the panel end		
seaming). Next lock down the first station handle, followed by	laps. The end laps should be hand crimped for a proper		
the fourth station handle.	finished seam.		

## Single Directional QuadLok Seamer







Hand Crimped QuadLok Seam

Hand Crimper RollLok/TripleLok Seam Make sure this roller is engaging the panel as shown.

17.0 QUADLOK SEAMING DETAILS (DOUBLE PASS OPERATION)	Next lock down the first station handle, followed by the fourth station handle.		
<b>17.1 Prior to Seaming</b> Prior to QuadLok seaming, the roof panels <b>MUST</b> have been fully TripleLok seamed. This is accomplished with the Primary motorized three or for station seaming machine. <b>In order to</b> <b>achieve a good QuadLok seam, you MUST first have a good</b> <b>TripleLok seam.</b> Inspect ALL TripleLok seams PRIOR to running the QuadLok seamer. Questionable TripleLok seams should be re-crimped with the hand crimper or motorized seamed again with the (Definition of Comparison)	<ul> <li>Finish by locking down handles 2 &amp; 3. Make sure that the number one station has engaged the panel (as shown below in Figure 34).</li> <li><b>17.3 Motor Seaming</b></li> <li>Once the seamer is properly locked on the pre-crimped seam, switch the machine on and seam the full length of each roof panel.</li> </ul>		
<ul> <li>with the "Primary Seamer" (TripleLok).</li> <li><b>17.2 Locking Seamer on Panel</b></li> <li>Prior to running a single directional QuadLok seamer, you</li> <li><b>MUST</b> hand crimp a small area with a QuadLok hand crimper as described in Section 16.0. After the QuadLok hand crimping had been completed, place the QuadLok seamer on the panel rib, aligning the number four station roller over the previously QuadLok hand crimped area. (NOTE: Make sure the arrow on the seamer is pointing in the direction you are seaming).</li> </ul>	The seamer will run from eave to ridge OR ridge to eave, depending on the way the roof panels were installed. <b>NOTE:</b> It is recommended <b>NOT</b> to run the seamer over the panel end laps. The end laps should be hand crimped for a proper finished seam. <b>17.4 Finished Seam Detail</b> Check that the finished seam is correctly formed as shown in the detail below.		



Figure 34



Finished QuadLok Seam

Four Station QuadLok Seamer

(Double Pass Operation)



#### 18.0 MOTORIZED SEAMING MACHINE MAINTENANCE

#### 18.1 General

The motorized seaming machine is a precision fabricated, high performance, portable roll-forming machine. This relatively lightweight machine does the tough job of forming the extra strong TripleLok and QuadLok seams under often rugged field conditions.

Although designed for tough industrial use, the seaming machine requires proper maintenance to assure proper seaming and efficient, trouble-free operation.

# CAUTION: Failure to properly maintain the seaming machine, as instructed below, can result in faulty or damaged seams and costly breakdown of the seaming machine.

#### 18.2 Seaming Rolls

The seaming rolls require the following regular maintenance:

- Assure that the seaming machine's rolls are clear of dirt, grease, sealant, and Galvalume/paint build-up, etc. Rollers may be cleaned with mineral spirits. Please follow manufacturer's instructions when using mineral spirits. Make sure rollers are clear of mastic and dry before seaming.
- > Assure that the seaming machine's rolls are tight on their shafts. Check and tighten the rolls retainer screws as necessary.

#### 18.3 Cooling Vents

To prevent motor overheating, the motor has vents and an internal fan to provide a cooling airflow over the internal motor ports.

The cooling vents are located at the front and rear of the motor. At the front of the motor, the vents are the slots between the motor housing and gear box. The rear vents are on the end of the motor housing. Check frequently to assure that these vents are kept clean and clear of debris and string sealant, etc.

While the machine is running, never cover the machine or place it in a position where the cooling airflow to the vents will be restricted.

#### 19.0 SEAMER TROUBLESHOOTING GUIDE

The chart below is a list of possible problems and solutions. *If you cannot resolve the problem with this chart, STOP work immediately and contact either Horizon Structural Systems Customer Service or a representative from the seamer* 

supplier. Seaming Problem	Possible Cause	Look For	Recommended Fix
Seaming machine drags, stalls at clips, runs intermittently, or won't run at all.	Extension cord too long and/or not heavy enough gauge.	<ul><li>7+ amps at the motor with no load (locking handle locked).</li><li>10+ amps at the motor during</li></ul>	Use a shorter and heavier gauge extension cord.
		seaming (between clips).	
	Generator is not suppling the proper amps to the seamer.	7+ amps at the motor with no load (locking handle locked).	Use a larger generator.
		10+ amps at the motor during seaming (between clips).	
	Faulty motor.	7+ amps at the motor with no load (locking handle locked).	Notify HSS or the seamer supplier for a replacement unit.
		10+ amps at the motor during seaming (between clips).	
	Seam is NOT crimped.	Un-crimped areas.	Complete a RollLok seam
Seam hook is not closed or improper nesting of the male to female and/or clip.	Excess panel coverage width. MUST be held 24-inches O.C.	Cladding or paint deposits on forming rollers.	Ensure correct panel coverage width at installation.
	Incorrect profile or damaged (deformed) clip or male/female panel leg.	Seam does not appear to be fully engaged.	Correct the profile of the male/female panel leg. If necessary, hand crimp the corrected area.
Creasing, scuffing, etched line along atop of seam, and/or deformation of seam.	Cam roller does not turn freely.	Cam roller bearing frozen, or fouled by sealant or debris.	Clean and lubricate or replace the cam roller.
Cladding/paint pick-off.	Incorrect profile or damaged	Seam does not appear to be	Correct the profile of the clip
	(deformed) clip or male/female panel leg.	fully engaged.	or male/female panel leg. Hand crimp the corrected area.
	Excess panel coverage width.	Cladding or paint deposits on forming rollers.	Ensure correct panel coverage width during installation.